

Student Center AcquiSuite handover

DATE September 14, 2026
PREPARED BY Northlake University

Provided by Northlake Facilities Operations. Packet 0.3. All readings are synthetic.

The Student Center electric meter is **SYN-VED-M-0040004**, on Valley Electric account **SYN-VED-A-0010004**. Its logger serial is **ASQVED01** and its device identifier is **STUDENT**. Files use the name **ASQVED01_STUDENT.log**.

File specification

There is **no header row**. Each line contains these comma-separated fields:

Position	Measurement	Unit	Meaning
0	Timestamp	UTC	Start of the 15-minute interval, enclosed in single quotes
1	Delivered energy	kWh	Energy used during this interval; not a cumulative register
2	Average demand	kW	Average power during the same interval

The complete sample represents January 15, 2024 in Sacramento, from **00:00 to 23:45 PST**. UTC timestamps run from **2024-01-15 08:00:00** through **2024-01-16 07:45:00**. No DST transition occurs in this sample.

The values describe a simplified operating day: 40 kW overnight, 80 kW during morning opening, 120 kW during the working day, 100 kW in the evening, and 60 kW late at night. Every interval's kWh equals its average kW multiplied by 0.25 hours.

Supplied deliveries

Folder	Rows	Energy	Peak demand	Purpose
complete/	96	2,020 kWh	120 kW	One complete day; also use the same file again for replay testing
gap/	88	1,780 kWh	120 kW	Eight missing intervals, from 12:00 through 13:45 PST
backfill/	8	240 kWh	120 kW	Only the missing intervals

expected-results.json includes file hashes and expected counts. There are two measurements per row, so the complete file supplies 192 point readings. Adding the backfill to the gap must recover the complete day's 96 timestamps per point and 2,020 kWh. Replaying the complete file must not increase unique timestamps or energy totals.

Deliver **one case at a time**. The complete run and the gap/backfill run start from separate copies of the same configured, empty baseline. These three folders are alternative deliveries, not three independent meters or days.

The file has been generated and checked against its expected values. Installed gateway execution, data storage, reports and replay behavior still require the implementation team's acceptance run. The accompanying [UI checklist](#) describes that run.